

数量総括表

| 工 事 名 | (路4-5)路面復旧工事 | | | 事 業 区 分 | | | | | | |
|------------|--------------|--------|---------|-----------------------------------|----|--------|------|------|------|-------------------|
| | | | | 工 事 区 分 | | | | | | |
| 工事区分(1) | 工種 (2) | 種別 (3) | 細 別 (4) | 規 格 (5) | 単位 | 実施数量 | 計上数量 | 変更数量 | 計上数量 | 摘 要 |
| 舗装 | | | | | | | | | | |
| 舗装工 | | | | | | | | | | |
| 舗装準備工 | | | | | | | | | | |
| 不陸整正 | | | | 補足材M-30 t=3cm 平均幅員W＞3.0m | m2 | 2160.6 | 2160 | | | 2056.27+104.33 |
| 不陸整正 | | | | 補足材M-30 t=3cm 平均幅員1.4m≦W≦3.0m | m2 | 830.9 | 831 | | | 496.51+334.37 |
| アスファルト舗装工 | | | | | | | | | | |
| 表層(車道・路肩部) | | | | 再生密粒度As(13) t=5cm 平均幅員W＞3.0m | m2 | 2160.6 | 2160 | | | 2056.27+104.33 |
| 表層(車道・路肩部) | | | | 再生密粒度As(13) t=5cm 平均幅員1.4m≦W≦3.0m | m2 | 830.9 | 831 | | | 496.51+334.37 |
| 区画線工 | | | | | | | | | | |
| 区画線工 | | | | | | | | | | |
| 溶融式区画線 | | | | 実線 白 W=15cm | m | 477.5 | 480 | | | 466.20+11.25 |
| 溶融式区画線 | | | | 実線 黄 W=15cm | m | 5.6 | 6 | | | |
| 溶融式区画線 | | | | ゼブラ 白 W=45cm | m | 31.5 | 32 | | | 29.35+2.1 |
| 溶融式区画線 | | | | 文字等 白 15cm換算 | m | 25.7 | 26 | | | 7.5×2+10.7 |
| 溶融式区画線 | | | | 文字等 黄 15cm換算 | m | 58.0 | 58 | | | |
| 構造物撤去工 | | | | | | | | | | |
| 構造物取壊し工 | | | | | | | | | | |
| 舗装版切断 | | | | As舗装版 t≦15cm | m | 479.3 | 480 | | | 340.2+17.5+121.55 |
| 舗装版破砕 | | | | As舗装版 t≦15cm 平均幅員W＞3.0m | m2 | 2160.6 | 2160 | | | 2056.27+104.33 |
| 舗装版破砕 | | | | As舗装版 t≦15cm 平均幅員1.4m≦W≦3.0m | m2 | 830.9 | 830 | | | 496.51+334.37 |
| 運搬処理工 | | | | | | | | | | |
| 殻運搬 | | | | As舗装版殻 平均幅員W＞3.0m | m3 | 108.0 | 108 | | | 2160.6*0.05 |
| 殻運搬 | | | | As舗装版殻 平均幅員1.4m≦W≦3.0m | m3 | 41.5 | 42 | | | 830.9*0.05 |
| 濁水運搬 | | | | As舗装版濁水 | 式 | 1.0 | 1 | | | |
| 殻処分 | | | | As舗装版殻 | m3 | 149.6 | 150 | | | |
| 濁水処分 | | | | As舗装版濁水 | m3 | 0.550 | 0.55 | | | 0.39+0.02+0.14 |

| 工事区分(1) | 工種 (2) | 種別 (3) | 細 別 (4) | 規 格 (5) | 単位 | 実施数量 | 計上数量 | 変更数量 | 計上数量 | 摘 要 |
|---------|--------|--------|---------|------------------------|----|-------|------|------|------|-------------|
| | | | 付帯工 | | | | | | | |
| | | | 付帯工 | | | | | | | |
| | | | 付帯工 | | 式 | 1.0 | 1 | | | |
| | | | 交差点鉾 | NML-1N12、八面反射、設置幅200mm | 個 | 2.0 | 2 | | | |
| | | | 境界点設置工 | 金属鉾 | 点 | 8.0 | 8 | | | |
| | | | 基準点設置工 | 金属鉾 | 点 | 9.0 | 9 | | | 3+5+1 |
| | | | 路面カラー塗装 | 200m2以上、2回塗り | m2 | 201.3 | 201 | | | 197.47+3.86 |
| | | | 仮設工 | | | | | | | |
| | | | 交通管理工 | | | | | | | |
| | | | 交通誘導警備員 | | 式 | 1.0 | 1 | | | |

路線1-1 舗装工計算書

[illegible]

路線1-1 舗装工計算書

[illegible]

路線1-1 舗装工計算書

[illegible]

路線1-1 舗装工計算書

[illegible]

路線1-1 舗装工計算書

| 測点 (BP1～EP1) | 単距離 | 表層工 再生密粒度ASC | | | | 控除面積 マンホール等 | | | |
|-----------------|-------------|-----------------|--------|--|--|----------------|-----------------|----------------------|--|
| | (m) | 巾(m) | 面積(m2) | | | 名称 | (1箇所) 面積(m2) | | |
| +9.80 | 2.60 | 5.60 | 14.50 | | | | | | |
| +9.80 | 0.00 | 6.45 | 0.00 | | | | | | |
| EP1 (+11.75) | 1.95 | 6.45 | 12.58 | | | | | | |
| | | | | | | | | | |
| ①三斜求積 | | | 70.55 | | | | | | |
| ②三斜求積 | | | 9.44 | | | | | | |
| ③三斜求積 | | | 23.14 | | | | | | |
| ④三斜求積 | | | 13.97 | | | | | | |
| ⑤三斜求積 | | | 11.34 | | | | | | |
| ⑥三斜求積 | | | 22.53 | | | | | | |
| ⑦三斜求積 | | | 9.10 | | | | | | |
| ⑧三斜求積 | | | 13.30 | | | | | | |
| ⑨三斜求積 | | | 17.84 | | | | | | |
| ⑩三斜求積 | | | 27.84 | | | | | | |
| ⑪三斜求積 | | | 15.15 | | | | | | |
| ⑫三斜求積 | | | 49.96 | | | | | | |
| ⑬三斜求積 | | | 0.96 | | | | | | |
| ⑭三斜求積 | | | 13.36 | | | | | | |
| ⑮三斜求積 | | | 5.77 | | | | | | |
| ⑯三斜求積 | | | 7.12 | | | | | | |
| ⑰三斜求積 | | | 15.85 | | | | | | |
| ⑱三斜求積 | | | 28.54 | | | | | | |
| ⑲三斜求積 | | | 11.84 | | | | | | |
| ⑳三斜求積 | | | 21.33 | | | | | | |
| ㉑三斜求積 | | | 30.24 | | | | | | |
| 合計 | m 491.75 | m2 2072.68 | | | | m2 16.41 | | 舗装合計(控除済) 2056.27 | |

路線1-1 舗装工計算書

| 測点 (BP2～EP2) | 単距離 | 表層工 再生密粒度ASC | | | | 控除面積 マンホール等 | | | |
|-----------------|------------|-----------------|--------|--|--|------------------|-----------------|---------------------|--|
| | (m) | 巾(m) | 面積(m2) | | | 名称 | (1箇所) 面積(m2) | | |
| BP2 | 0.00 | 0.00 | | | | 止水弁 φ370*3 | (0.11) 0.33 | | |
| +0.50 | 0.50 | 4.00 | 1.00 | | | 量水器 500*300*1 | 0.15 | | |
| +15.70 | 15.20 | 4.00 | 60.80 | | | 集水桝 400*400*1 | 0.16 | | |
| +15.70 | 0.00 | 5.50 | 0.00 | | | | | | |
| +17.20 | 1.50 | 5.50 | 8.25 | | | | | | |
| +17.20 | 0.00 | 4.85 | 0.00 | | | | | | |
| NO.1 | 2.80 | 4.85 | 13.58 | | | | | | |
| EP2 (+4.40) | 4.40 | 4.85 | 21.34 | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| 合計 | m 24.40 | m2 104.97 | | | | m2 0.64 | | 舗装合計(控除済) 104.33 | |

路線1-1 舗装版切断工数量計算書

| 工 種 | 規 格 | 数 量 | 摘 要 |
|-----|-------------------|-------|--------|
| | アスファルト版 (t =5cm) | | |
| ① | | 4.40 | |
| ② | | 3.30 | |
| ③ | | 1.65 | |
| ④ | | 2.05 | |
| ⑤ | | 1.60 | |
| ⑥ | | 3.25 | |
| ⑦ | | 4.90 | |
| ⑧ | | 6.10 | |
| ⑨ | | 4.50 | |
| ⑩ | | 3.95 | |
| ⑪ | | 3.90 | |
| ⑫ | | 4.00 | |
| ⑬ | | 4.85 | |
| ⑭ | | 2.10 | |
| ⑮ | | 3.30 | |
| ⑯ | | 3.35 | |
| ⑰ | | 2.70 | |
| ⑱ | | 66.50 | (センター) |
| ⑲ | | 2.65 | |
| ⑳ | | 4.80 | |
| ㉑ | | 2.70 | |
| ㉒ | | 3.40 | |
| ㉓ | | 2.70 | |
| ㉔ | | 2.70 | |
| ㉕ | | 8.25 | (センター) |
| ㉖ | | 7.95 | |
| ㉗ | | 2.60 | |
| ㉘ | | 2.55 | |
| ㉙ | | 2.65 | |
| ㉚ | | 75.40 | (センター) |
| ㉛ | | 2.55 | |
| ㉜ | | 2.70 | |
| ㉝ | | 2.70 | |
| ㉞ | | 3.90 | |
| ㉟ | | 5.50 | (センター) |
| ㊱ | | 2.15 | |

路線1-1 舗装版切断工数量計算書

[illegible]

路線1-1 区画線工数量計算書

| 工 種 | 規 格 | 数 量 | 摘 要 |
|------|-----------------|----------|-----|
| | 実線 15cm幅 白 | | |
| ①外側線 | | 9.00 | |
| ②外側線 | | 83.80 | |
| ③外側線 | | 48.00 | |
| ④外側線 | | 2.55 | |
| ⑤外側線 | | 35.60 | |
| ⑥外側線 | | 11.70 | |
| ⑦外側線 | | 1.40 | |
| ⑧外側線 | | 20.20 | |
| ⑨外側線 | | 24.00 | |
| ⑩外側線 | | 3.40 | |
| ⑪外側線 | | 16.70 | |
| ⑫外側線 | | 3.85 | |
| ⑬外側線 | | 8.10 | |
| ⑭外側線 | (3.15+5.20) | 8.35 | |
| ⑮外側線 | | 13.50 | |
| ⑯外側線 | | 2.70 | |
| ⑰外側線 | | 4.95 | |
| ⑱外側線 | | 23.30 | |
| ⑲外側線 | | 7.40 | |
| ⑳外側線 | | 23.30 | |
| ㉑外側線 | | 11.25 | |
| ㉒外側線 | | 17.90 | |
| ㉓外側線 | | 3.60 | |
| ㉔外側線 | | 43.00 | |
| ㉕外側線 | | 9.75 | |
| ㉖外側線 | | 17.35 | |
| ㉗外側線 | (0.90+7.65) | 8.55 | |
| ①白線 | (1.00*3・1m置き) | 3.00 | |
| | 合計 | 466.20 m | |
| | | | |
| | 実線 15cm幅 黄 | | |
| ①消火栓 | (0.90*2+0.50*2) | 2.80 | |
| ②消火栓 | (0.90*2+0.50*2) | 2.80 | |
| | 合計 | 5.60 m | |

路線1-1 区画線工数量計算書

[illegible]

路線1-1 付帯工数量計算書

[illegible]

路線1-2 舗装工計算書

| 測点 (BP1～EP1) | 単距離 | 表層工 再生密粒度ASC | | | | 控除面積 マンホール等 | | | |
|-----------------|-------------|-----------------|-----------|--|--|---------------------|-----------------|---------------------|--|
| | (m) | 巾(m) | 面積(m2) | | | 名称 | (1箇所) 面積(m2) | | |
| BP1 | 0.00 | | | | | 仕切弁 φ 370*3 | (0.11) 0.33 | | |
| +6.05 | 6.05 | 2.65 | ① 三斜求積 | | | 下水マンホール φ 1000*1 | 0.79 | | |
| NO. 1 | 13.95 | 2.60 | 36.62 | | | 下水マンホール φ 800*3 | (0.50) 1.50 | | |
| NO. 2 | 20.00 | 2.60 | 52.00 | | | 止水栓 φ 160*1 | 0.02 | | |
| +17.75 | 17.75 | 2.55 | 45.71 | | | | | | |
| NO. 3 | 2.25 | 0.00 | | | | | | | |
| +3.00 | 3.00 | 3.40 | ② 三斜求積 | | | | | | |
| NO. 4 | 17.00 | 3.40 | 57.80 | | | | | | |
| +12.40 | 12.40 | 3.45 | 42.47 | | | | | | |
| +12.40 | 0.00 | 3.00 | 0.00 | | | | | | |
| +16.65 | 4.25 | 2.95 | 12.64 | | | | | | |
| +16.65 | 0.00 | 3.40 | 0.00 | | | | | | |
| NO. 5 | 3.35 | 3.40 | 11.39 | | | | | | |
| EP1 (+11.95) | 11.95 | 3.40 | 40.63 | | | | | | |
| | | | | | | | | | |
| ①三斜求積 | | | 63.03 | | | | | | |
| ②三斜求積 | | | 20.14 | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| 合計 | m 111.95 | m2 382.43 | | | | m2 2.64 | | 舗装合計（控除済） 379.79 | |

路線1-2 舗装工計算書

| 測 点 (BP2～EP2) | 単距離 | 表層工 再生密粒度ASC | | | | 控除面積 マンホール等 | | | |
|------------------|------------|-----------------|--------|--|--|--------------------|-----------------|---------------------|--|
| | (m) | 巾(m) | 面積(m2) | | | 名称 | (1箇所) 面積(m2) | | |
| BP2 | 0.00 | 0.00 | | | | 仕切弁 φ 370*2 | (0.11) 0.22 | | |
| +0.25 | 0.25 | 2.60 | 0.33 | | | 下水マンホール φ 700*1 | 0.38 | | |
| NO. 1 | 19.75 | 2.50 | 50.36 | | | 下水マンホール φ 800*1 | 0.50 | | |
| NO. 2 | 20.00 | 2.40 | 49.00 | | | 止水栓 φ 160*1 | 0.02 | | |
| +7.95 | 7.95 | 2.35 | 18.88 | | | 汚水枡 φ 170*1 | 0.02 | | |
| EP2 (+8.50) | 0.55 | 0.00 | 0.65 | | | 集水枡 580*580*4 | (0.34) 1.36 | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| 合計 | m 48.50 | m2 119.22 | | | | m2 2.50 | | 舗装合計（控除済） 116.72 | |

路線1-2 舗装版切断工数量計算書

[illegible]

路線1-2 付帯工数量計算書

[illegible]

路線1-3 舗装工計算書

| 測 点 | 単距離 | 表層工 再生密粒度ASC | | | | 控除面積 マンホール等 | | | |
|------------|-------------|-----------------|-----------|--|--|---------------------|-----------------|---------------------|--|
| | (m) | 巾(m) | 面積(m2) | | | 名称 | (1箇所) 面積(m2) | | |
| BP2 | 0.00 | | | | | 仕切弁 φ 370*2 | (0.11) 0.22 | | |
| +2.70 | 2.70 | 2.65 | ① 三斜求積 | | | 下水マンホール φ 700*1 | 0.38 | | |
| NO. 1 | 17.30 | 2.65 | 45.85 | | | 下水マンホール φ 800*2 | (0.50) 1.00 | | |
| NO. 2 | 20.00 | 2.65 | 53.00 | | | 下水マンホール φ 1000*1 | 0.79 | | |
| +17.90 | 17.90 | 2.65 | 47.44 | | | 止水栓 φ 160*2 | (0.02) 0.04 | | |
| +17.90 | 0.00 | 5.30 | 0.00 | | | | | | |
| NO. 3 | 2.10 | 5.30 | 11.13 | | | | | | |
| +0.60 | 0.60 | 5.30 | 3.18 | | | | | | |
| +0.60 | 0.00 | 2.65 | 0.00 | | | | | | |
| NO. 4 | 19.40 | 2.65 | 51.41 | | | | | | |
| NO. 5 | 20.00 | 2.65 | 53.00 | | | | | | |
| +1.30 | 1.30 | 2.65 | 3.45 | | | | | | |
| +1.30 | 0.00 | 5.30 | 0.00 | | | | | | |
| +2.65 | 1.35 | 5.30 | 7.16 | | | | | | |
| EP (+8.30) | 5.65 | 0.00 | ② 三斜求積 | | | | | | |
| | | | | | | | | | |
| ①三斜求積 | | | 16.67 | | | | | | |
| ②三斜求積 | | | 44.51 | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| 合計 | m 108.30 | m2 336.80 | | | | m2 2.43 | | 舗装合計（控除済） 334.37 | |

路線1-3 舗装版切断工数量計算書

[illegible]

路線1-3 区画線工数量計算書

[illegible]

路線1-3 付帯工数量計算書

[illegible]