

数量総括表

工 事 名	(路4-6)路面復旧工事			事 業 区 分		
				工 事 区 分		
工事区分(1) 工種 (2) 種別 (3)	細 別 (4)	規 格 (5)	単位	実施数量	計上数量	摘 要
【路線1】舗装						
道路土工(夜間)						
掘削工						
掘削			m3	2.2	2	8.71*0.25
土砂等運搬	現場～仮置き場		m3	2.2	2	
積込ルーズ	土砂		m3	2.2	2	昼
土砂等運搬	仮置き場～処分場		m3	2.2	2	昼
舗装工						
舗装準備工						
不陸整正	補足材M-30 t=3cm		m2	859.7	860	854.5+5.2
アスファルト舗装工(車道部)						
表層(車道・路肩部)	再生密粒度As(13) t=5cm 平均幅員1.4m≦W≦3.0m		m2	854.5	855	
表層(車道・路肩部)	開粒度As(13) t=5cm 平均幅員1.4m≦W≦3.0m		m2	5.2	5	
舗装工(夜間)						
舗装準備工						
不陸整正(歩道部)	補足材M-30 t=3cm		m2	9.2	9	3.2+6.0
アスファルト舗装工(車道部)						
上層路盤(車道・路肩部)	M40-0 t=25cm		m2	8.7	9	
瀝青安定処理(車道・路肩部)	瀝青安定処理路盤材 t=8cm		m2	8.7	9	
基層(車道・路肩部)	再生粗粒度As(20) t=5cm		m2	8.7	9	
表層(車道・路肩部)	改質Ⅱ型 t=5cm		m2	15.0	15	
アスファルト舗装工(歩道部)						
表層(歩道部)	開粒度As(13) t=4cm 平均幅員1.4m未満		m2	6.0	6	
表層(歩道部)	開粒度As(13) t=3cm 平均幅員1.4m未満		m2	3.2	3	
区画線工						
区画線工						
熔融式区画線	実線 白 W=15cm		m	5.5	6	
熔融式区画線	実線 黄 W=15cm		m	2.8	3	
熔融式区画線	実線 白 W=30cm		m	2.3	2	
熔融式区画線	ゼブラ 白 W=45cm		m	9.2	9	
熔融式区画線	文字等 白 15cm換算		m	42.0	42	
構造物撤去工						
構造物取壊し工						
舗装版切断	As舗装版 t≦15cm		m	38.8	39	
舗装版切断	As舗装版 15cm<t		m	8.5	9	
舗装版破碎	As舗装版 t≦15cm		m2	859.7	860	854.5+5.2

数量総括表

工 事 名	(路4-6)路面復旧工事			事 業 区 分		
				工 事 区 分		
工事区分(1) 工種 (2) 種別 (3) 細 別 (4)	規 格 (5)	単位	実施数量	計上数量	摘 要	
運搬処理工						
殻運搬	As舗装版殻	m3	43.0	43	859.7*0.05	
濁水運搬	As舗装版濁水	式	1.0	1		
殻処分	As舗装版殻	m3	45.2	45	43.0+2.2	
濁水処分	As舗装版濁水	m3	0.080	0.08		
構造物撤去工(夜間)						
構造物取壊し工						
舗装版破碎	As舗装版 t≤15cm	m2	15.5	16	6.3+3.2+6.0	
舗装版破碎	As舗装版 15cm<t	m2	8.7	9		
運搬処理工						
殻運搬	As舗装版殻 現場～仮置き場	m3	2.2	2	6.3*0.05+8.7*0.18+3.2*0.03+6.0*0.04	
積込ルーズ	岩塊・玉石	m3	2.2	2	昼	
殻運搬	As舗装版殻 仮置き場～処分場	m3	2.2	2	昼	
付帯工						
付帯工						
付帯工		式				
基準点設置工	金属鋲	点	2.0	2		
薄層カラー舗装	赤	m2	33.0	33		
仮設工						
交通管理工						
交通誘導警備員		式	1.0	1		

路線1 舗装工計算書

測点 (BP1～EP1)	単距離	表層工 再生密粒度ASC				控除面積 マンホール等			
	(m)	巾(m)	面積(m2)			名称	(1箇所) 面積(m2)		
BP+4.00	0.00	1.40				仕切弁 φ370*7	(0.11) 0.77		
+10.00	6.00	1.10	7.50			仕切弁 600*600	0.36		
+15.00	5.00	1.00	5.25			仕切弁 600*1200	0.72		
NO.1	5.00	1.60	6.50			止水栓 φ160*2	(0.02) 0.04		
+10.00	10.00	2.10	18.50			空気弁 φ520	0.21		
NO.2	10.00	2.00	20.50			消火栓 φ520	0.21		
+8.70	8.70	2.30	18.71			汚水枳 φ300	0.07		
+8.70	0.00	3.40	0.00			下水マンホール φ700*16	(0.38) 6.08		
+10.00	1.30	3.30	4.36						
NO.3	10.00	3.80	35.50						
+4.70	4.70	4.00	18.33						
+10.00	5.30	3.50	19.88						
NO.4	10.00	3.10	33.00						
+10.00	10.00	2.90	30.00						
NO.5	10.00	2.80	28.50						
+10.00	10.00	3.20	30.00						
+15.50	5.50	3.20	17.60						
NO.7+5.10	0.00	2.60	0.00						
+10.00	4.90	2.50	12.50						
NO.8	10.00	2.60	25.50						
+10.00	10.00	2.60	26.00						
NO.9	10.00	2.50	25.50						
+10.00	10.00	2.70	26.00						
+19.20	9.20	2.50	23.92						
小計			433.6				8.46		

路線1 舗装工計算書

測点 (BP1～EP1)	単距離	表層工 再生密粒度ASC				控除面積 マンホール等			
	(m)	巾(m)	面積(m2)			名称	(1箇所) 面積(m2)		
+19.20	0.00	2.10	0.00						
NO. 10	0.80	2.10	1.68						
+10.00	10.00	2.10	21.00						
NO. 11	10.00	2.10	21.00						
+10.00	10.00	2.30	22.00						
NO. 12	10.00	2.50	24.00						
+10.00	10.00	2.80	26.50						
NO. 13	10.00	2.50	26.50						
+7.90	7.90	2.30	18.96						
+14.30	0.00	2.40	0.00						
NO. 14	5.70	2.50	13.97						
+2.00	2.00	2.90	5.40						
三斜①			11.87						
三斜②			10.99						
三斜③			105.80						
三斜④			3.80						
三斜⑤			5.40						
三斜⑥			5.88						
三斜⑦			4.32						
枝道①			27.09						
枝道③			24.63						
枝道④			34.29						
枝道⑤			14.36						
小計		429.4				0.00		舗装合計（控除済）	
合計		862.99				8.46		854.53	

路線1 枝道② 舗装工計算書

測 点 (BP1～EP1)	単距離	表層工				控除面積			
		開粒度ASC				マンホール等			
	(m)	巾(m)	面積(m2)			名称	(1箇所) 面積(m2)		
枝道②			5.18			止水栓 φ160	0.02		
合計			5.18				0.02	舗装合計（控除済） 5.16	

測点 (BP1～EP1)	単距離	表層工 改質Ⅱ型		基層工・瀝青安定 処理工・上層路盤 工		控除面積 マンホール等			
	(m)	巾(m)	面積(m2)			名称	(1箇所) 面積(m2)		
県道車道部			14.96		14.96				
				暗渠 控除	(6.25)				
合計			14.96		8.71		0.00	舗装合計（控除済） 14.96	

路線1 県道歩道部① 舗装工計算書

測点 (BP1～EP1)	単距離	表層工 開粒度ASC, t=4cm				控除面積 マンホール等			
	(m)	巾(m)	面積(m2)			名称	(1箇所) 面積(m2)		
県道歩道部①			6.31			仕切弁 550*450	0.25		
						電柱 φ320	0.08		
合計			6.31				0.33	舗装合計（控除済） 5.98	

路線1 県道歩道部② 舗装工計算書

測点 (BP1～EP1)	単距離	表層工 開粒度ASC, t=3cm				控除面積 マンホール等			
	(m)	巾(m)	面積(m2)			名称	(1箇所) 面積(m2)		
県道歩道部②			3.25			止水栓 φ160	0.02		
合計			3.25				0.02	舗装合計(控除済) 3.23	

路線1 舗装版切断工数量計算書

[illegible]

路線1 区画線工数量計算書

[illegible]

路線1 付帯工数量計算書

[illegible]