

数量総括表

工 事 名	(路4-6)路面復旧工事			事 業 区 分		摘 要
				工 事 区 分		
工事区分(1) 工種 (2) 種別 (3)	細 別 (4)	規 格 (5)	単位	実施数量	計上数量	
【路線2】舗装						
舗装工						
舗装準備工						
不陸整正		補足材M-30 t=3cm	m2	993.3	993	760.14 + 233.17
アスファルト舗装工(車道部)						
表層(車道・路肩部)		再生密粒度As(13) t=5cm W=3.0m超え	m2	993.3	993	
区画線工						
区画線工						
溶融式区画線		実線 白 W=15cm	m	307.7	310	253.7 + 54
溶融式区画線		実線 黄 W=15cm	m	5.6	6	2.8 + 2.8
溶融式区画線		ゼブラ 白 W=45cm	m	12.0		
溶融式区画線		破線 白 W=15cm	m	30.0	30	
溶融式区画線		文字等 白 15cm換算	m	23.0	23	
構造物撤去工						
構造物取壊し工						
舗装版切断		As舗装版 t≤15cm	m	108.6	110	24.92 + 83.7
舗装版破砕		As舗装版 t≤15cm	m2	993.3	990	
運搬処理工						
殻運搬		As舗装版殻	m3	49.7	50	破砕面積*0.05
濁水運搬		As舗装版濁水	式	1.0	1	
殻処分		As舗装版殻	m3	49.7	50	
濁水処分		As舗装版濁水	m3	0.12	0.13	0.03 + 0.10
付帯工						
付帯工						
付帯工			式			
基準点設置工		金属鋲	点	1.0	1	
仮設工						
交通管理工						
交通誘導警備員			式	1.0	1	

路線2-1 舗装工計算書

測点 (BP1～EP1)	単距離	表層工 再生密粒度ASC				控除面積 マンホール等			
	(m)	巾(m)	面積(m2)			名称	(1箇所) 面積(m2)		
B. P-1. 90	0. 00	0. 00				仕切弁 φ 370*8	(0. 11) 0. 88		
B. P+1. 87	3. 77	4. 66	8. 78			止水栓 φ 160	0. 02		
NO. 1	18. 13	4. 55	83. 49			消火栓 620*530	0. 33		
+14. 75	14. 75	4. 47	66. 52			下水マンホール φ 550	0. 24		
+15. 74	0. 99	4. 53	4. 46						
+15. 74	0. 00	4. 71	0. 00						
NO. 2	4. 26	4. 80	20. 26						
+8. 07	8. 07	4. 97	39. 42						
NO. 3	11. 93	5. 01	59. 53						
+6. 66	6. 66	5. 00	33. 33						
+18. 28	11. 62	4. 88	57. 40						
+18. 28	0. 00	4. 76	0. 00						
+19. 07	0. 79	4. 76	3. 76						
+19. 07	0. 00	4. 88	0. 00						
NO. 4	0. 93	4. 87	4. 53						
+1. 06	1. 06	4. 93	5. 19						
NO. 5	18. 94	4. 86	92. 71						
+1. 07	1. 07	5. 02	5. 29						
+4. 02	2. 95	5. 08	14. 90						
+13. 65	9. 63	5. 11	49. 06						
+17. 06	3. 41	5. 02	17. 27						
+17. 78	0. 72	5. 17	3. 67						
+19. 15	1. 37	5. 43	7. 26						
NO. 6	0. 85	5. 47	4. 63						
+4. 02	4. 02	5. 69	22. 43						
+4. 81	0. 79	5. 38	4. 37						
小計		608. 26				1. 47			

路線2-1 舗装工計算書

測点 (BP1～EP1)	単距離	表層工 再生密粒度ASC				控除面積 マンホール等			
	(m)	巾(m)	面積(m2)			名称	(1箇所) 面積(m2)		
+4.81	0.00	5.33	0.00						
+5.47	0.66	5.26	3.49						
+5.79	0.32	5.29	1.69						
+6.67	0.88	5.19	4.61						
NO. 7	13.33	4.96	67.65						
三斜①			32.16						
三斜②			1.39						
三斜③			42.36						
小計			153.35				0.00	舗装合計（控除済）	
合計			761.61				1.47	760.14	

路線2-2 舗装工計算書

測 点	単距離	表層工 再生密粒度ASC				控除面積 マンホール等			
	(m)	巾 (m)	面積 (m2)			名称	(1箇所) 面積 (m2)		
B. P	0.00	3.10				仕切弁 φ 370*2	(0.11) 0.22		
NO. 1	20.00	3.10	62.00			消火栓 500*600	0.30		
+13.00	13.00	3.60	43.55			下水 φ 390	0.12		
+18.00	5.00	3.20	17.00						
NO. 2	2.00	3.40	6.60						
+3.50	3.50	3.70	12.43						
+4.20	0.70	3.70	2.59						
+9.00	4.80	3.50	17.28						
+9.00	0.00	6.70	0.00						
+18.40	9.40	6.50	62.04						
NO. 3	1.60	6.40	10.32						
小計		233.81				0.64		舗装合計 (控除済)	
合計		233.81				0.64		233.17	

路線2-1 舗装版切断工数量計算書

[illegible]

路線2-2 舗装版切断工数量計算書

[illegible]

路線2-1 区画線工数量計算書

[illegible]

路線2-2 区画線工数量計算書

[illegible]

路線2-1 付帯工数量計算書

[illegible]