

数量総括表

工 事 名	(路4-9)路面復旧工事(余フ)			事業区分		摘 要
				工事区分		
工事区分(1) 工種 (2) 種別 (3) 細 別 (4)	規 格 (5)	単位	実施数量	計上数量		
舗装						
舗装工						
舗装準備工						
不陸整正	補足材M-30 t=3cm	m2	221.99	222		
不陸整正	補足材なし	m2	6.30	6		
アスファルト舗装工						
表層(車道・路肩部)	再生密粒度As(13) t=5cm 平均幅員1.4m≦W≦3.0m	m2	221.99	222		
コンクリート舗装工						
コンクリート舗装	18-8-20早強,t=10cm	m2	6.30	6		
溶接金網		m2	6.30	6		
路盤紙		m2	6.30	6		
構造物撤去工						
構造物取壊し工(アスファルト)						
舗装版切断	As舗装版 t≦15cm	m	27.15	27		
舗装版破砕	As舗装版 t≦15cm	m2	222.68	223	221.99+6.30-5.61	
						※三斜①部内訳
						全体面積 9.90のうち
						Co5.61 As4.29
構造物取壊し工(コンクリート)						
舗装版切断	Co舗装版 t≦15cm	m	4.50	5		
舗装版破砕	Co舗装版 t≦15cm	m2	5.61	6		
運搬処理工(アスファルト)						
殻運搬	As舗装版殻	m3	11.1	11	(221.99+6.30-5.61)*0.05	
濁水運搬	As舗装版濁水	式	1.0	1		
殻処分	As舗装版殻	m3	11.1	11	(221.99+6.30-5.61)*0.05	
濁水処分	As舗装版濁水	m3	0.031	0.03		
運搬処理工(コンクリート)						
殻運搬	Co舗装版殻	m3	0.56	0.6	5.61*0.10	
濁水運搬	Co舗装版濁水	式	1.0	1		
殻処分	Co舗装版殻	m3	0.56	0.6	5.61*0.10	
濁水処分	Co舗装版濁水	m3	0.01	0.01		
仮設工						
交通管理工						
交通誘導警備員		式	1.0	1		

舗装数量計算書(アスファルト)

測点 (BP1～EP1)	単距離	舗装面積				控除面積 マンホール等			
	(m)	巾(m)	面積(m2)			名称	(1箇所) 面積(m2)		
B. P +10.90	0.00	1.60							
B. P +16.65	5.75	1.55	9.06						
NO.1 +4.25	7.60	1.70	12.35						
NO.1 +8.55	4.30	2.20	8.39						
NO.2 +1.65	13.10	1.85	26.53						
NO.2 +5.40	3.75	1.50	6.28						
NO.2 +15.70	10.30	1.75	16.74						
NO.2 +19.75	4.05	1.90	7.39						
NO.3 +14.85	15.10	2.10	30.20						
NO.3 +14.85	0.00	4.80							
NO.4 +7.40	12.55	3.75	53.65						
E. P (NO.4 +13.50)	6.10	3.75	22.88			仕切弁 φ370	0.11		
三斜①			9.90						
三斜②			20.00			植木 φ1.8m	1.27		
合計		223.37				1.38		舗装合計（控除済） 221.99	

舗装数量計算書(コンクリート)

測 点 (BP1～EP1)	単距離	舗装面積				控除面積 マンホール等			
	(m)	巾(m)	面積(m2)			名称	(1箇所) 面積(m2)		
B. P	0.00	0.60				グレーチング部 0.6×0.4	0.24		
+10.90	10.90	0.60	6.54						
合計			6.54				0.24	舗装合計(控除済) 6.30	

舗装版切断工数量計算書

[illegible]