

数量総括表(R8-路3-02)

No.	施工 区分	舗装 構成	上層路盤		上層路盤		表 層		基層		舗装版破碎		As殻処分		舗装版切断		熔融式区画線											
			【昼・夜】 (不陸整正)		【夜】 (瀝青安定処理)		(PK-3使用) (PK-4使用)		(PK-4使用)		【昼】人力施工 【夜】機械施工		【昼】人力積込 【夜】機械積込		【昼】 (t=15cm以下) 【夜】 (15cm<t≤ 30cm)		【昼・夜】 白線 破線		【夜】 消火栓ライン		【夜】 文字・記号		【夜】 ゼブラ		【夜】 ゼブラ		【夜】 ゼブラ	
			粒調砕石(M30-0)		(PK-3使用)		再生密粒度アスコン		再生粗粒度アスコン								(W=15cm)		(W=15cm)		(W=15cm)		(W=15cm)		(W=20cm)		(W=30cm)	
			補足材 (t=3cm)		(t=10cm)		(t=5cm)		(t=5cm)																			
1	昼	A (5cm)	18.4	m ²		m ²	18.4	m ²		m ²	18.4	m ²	0.92	m ³	11.85	m	5.00	m		m		m		m		m		m
			3.5	m ²		m ²	3.5	m ²		m ²	3.5	m ²	0.18	m ³														
			7.9	m ²		m ²	7.9	m ²		m ²	7.9	m ²	0.40	m ³														
2	昼	A (5cm)	6.9	m ²		m ²	6.9	m ²		m ²	6.9	m ²	0.35	m ³	11.60	m		m		m		m		m		m		m
			3.9	m ²		m ²	3.9	m ²		m ²	3.9	m ²	0.20	m ³														
			7.2	m ²		m ²	7.2	m ²		m ²	7.2	m ²	0.36	m ³														
3	昼	A (5cm)	10.6	m ²		m ²	10.6	m ²		m ²	10.6	m ²	0.53	m ³	11.63	m		m		m		m		m		m		m
			14.7	m ²		m ²	14.7	m ²		m ²	14.7	m ²	0.74	m ³														
			37.7	m ²		m ²	37.7	m ²		m ²	37.7	m ²	1.89	m ³														
4	夜	C (20cm)	68.3	m ²	68.3	m ²	68.3	m ²	68.3	m ²	68.3	m ²	13.66	m ³	40.71	m	20.61	m	2.80	m	15.5642	m		m		m		m
5	夜	C (20cm)	107.8	m ²	107.8	m ²	107.8	m ²	107.8	m ²	107.8	m ²	21.56	m ³	61.60	m	59.50	m	2.80	m		m	0.6	m	0.6	m	1.2	m
昼間施工 合計			110.8	m ²	0.0	m ²	110.8	m ²	0.0	m ²	110.8	m ²	5.57	m ³	35.1	m	5.0	m	0.00	m	0.0	m	0.00	m	0.00	m	0.00	m
改め			111	m ²	0	m ²	111	m ²	0	m ²	111	m ²	6	m ³	35	m	5	m	0	m	0	m	0	m	0	m	0	m
夜間施工 合計			176.1	m ²	176.1	m ²	176.1	m ²	176.1	m ²	176.1	m ²	35.2	m ³	102.3	m	80.1	m	5.6	m	15.5642	m	0.60	m	0.60	m	1.20	m
改め			176	m ²	176	m ²	176	m ²	176	m ²	176	m ²	35	m ³	102	m	80	m	5.6	m	15.5642	m	0.60	m	0.60	m	1.20	m

※【昼】収集濁水量(m³) : 0.04

※【夜】収集濁水量(m³) : 0.47