

数量総括表

工 事 名		水路改良工事(その2)				事 業 区 分		農業施設等整備事業		
						工 事 区 分				
工事区分(1)	工種 (2)	種別 (3)	細 別 (4)	規 格 (5)	単位	実施数量	計上数量	変更数量	計上数量	摘 要
道路改良【1号箇所】										
道路土工										
作業土工										
床掘					m3	11.78	10			
埋戻し				M30-0	m3	0.40	0.4			
〃				RC40-0	m3	1.00	1			
〃				発生土	m3	1.70	2			
〃				砂	m3	0.60	0.6			
排水構造物工										
側溝工										
自由勾配側溝				縦断用 700*500	m	20.00	20			
側溝蓋				コンクリート蓋	枚	18.00	18			
〃				グレーチング	枚	2.00	2			
間詰コンクリート				18-8-25	m3	0.10	0.1			
目地板					m2	0.01	0.01			
構造物撤去工										
構造物取壊し工										
コンクリート構造物取壊し				無筋Co	m3	2.60	3			
〃				鉄筋Co	m3	0.71	0.7			
舗装版切断				As	m	21.21	21			20+0.71+0.5
舗装版破碎				As t=50	m2	14.20	14			
運搬処理工										
殻運搬処分				無筋Co殻	m3	2.60	3			
〃				鉄筋Co殻	m3	0.71	0.7			
〃				As殻 t=50	m3	0.71	0.7			14.2*0.05
土砂等運搬処分					m3	10.08	10			
濁水運搬処分					m3	0.024	0.02			21.21*0.05*0.023

工事区分(1)	工種(2)	種別(3)	細別(4)	規格(5)	単位	実施数量	計上数量	変更数量	計上数量	摘要
	舗装工									
	アスファルト舗装工									
	表層			再生密粒度As t=50	m2	10.00	10			
	付帯工									
	付帯工									
	コンクリート削孔			4孔	式	1.00	1			φ 75*2・φ 100*2
	排水管・暗渠管			4孔	式	1.00	1			〃
	車線分離標			撤去・再設置	本	2.00	2			
	仮設工									
	水替工									
	ポンプ排水				式	1.00	1			
	交通管理工									
	交通誘導警備員				人					
	道路改良【2号箇所】									
	道路土工									
	作業土工									
	床掘				m3	18.76	20			
	埋戻し			RC40-0	m3	18.76	20			
	軽量鋼矢板			H=2000	t	2.23	2.2			53.6*0.0416
	ガス切断				m	53.60	54			
	路肩整生			RC40-0	m2	11.00	10			
	コンクリート工									
	コンクリート工									
	天端コンクリート			18-8-25	m	53.60	54			
	目地板				m2	0.42	0.4			
	構造物撤去工									
	構造物取壊し工									
	コンクリート構造物取壊し			無筋Co	m3	3.22	3			
	運搬処理工									
	殻運搬処分			無筋Co	m3	3.22	3			
	土砂等運搬処分				m3	18.76	20			

[illegible]

土工数量計算書												1号箇所
測 点	距 離	床掘			埋戻 (M-30)			埋戻 (RC-40)			摘要	
		断面積	平 均	m3	断面積	平 均	m3	断面積	平 均	m3		
B.P		0.589			0.02			0.05				
+10.0	10.00	0.589	0.589	5.89	0.02	0.02	0.20	0.05	0.05	0.50		
No.1	10.00	0.589	0.589	5.89	0.02	0.02	0.20	0.05	0.05	0.50		
合計	20.00			11.78m3			0.40m3			1.00m3		
土工数量計算書												
測 点	距 離	埋戻 (建設発生土)			埋戻 (砂)						摘要	
		断面積	平 均	m3	断面積	平 均	m3					
B.P		0.085			0.03							
+10.0	10.00	0.085	0.085	0.85	0.03	0.03	0.30					
No.1	10.00	0.085	0.085	0.85	0.03	0.03	0.30					
合計	20.00			1.70m3			0.60m3					

測 点	距 離	基礎碎石 (RC40-0)			底張りCo			間詰Co		
		断面積	平 均	m3	断面積	平 均	m3	断面積	平 均	m3
B.P		0.111			0.097			0.005		
+10.0	10.00	0.111	0.111	1.11	0.097	0.097	0.97	0.005	0.005	0.05
+18.0	8.00	0.111	0.111	0.89	0.095	0.096	0.77	0.005	0.005	0.04
No.1	2.00	0.111	0.111	0.22	0.035	0.065	0.13	0.005	0.005	0.01
計	20.00			2.22m3			1.87m3			0.10m3

自由勾配側溝	縦断用 700*500*2000	20.00	m	1個2.0m
コンクリート基礎版	1060*100*2000	10.00	枚	
基礎碎石	RC40-0	2.22	m3	
底張りコンクリート	18-8-25	1.87	m3	
間詰コンクリート	18-8-25	0.10	m3	
側溝蓋	コンクリート蓋	18.00	枚	
側溝蓋	グレーチング	2.00	枚	
目地材	0.1*0.05*2	0.01	m2	

1号箇所											
構造物取壊し											
数 量 計 算 書											
測 点	距 離	無筋Co			鉄筋Co			舗装版破碎			摘要
		断面積	平 均	m3	断面積	平 均	m3	幅	平 均	m2	
B.P		0.13						0.71			
+3.7	3.70	0.13	0.13	0.48	0.085			0.71	0.71	2.63	
+10.0	6.30	0.13	0.13	0.82	0.085	0.085	0.54	0.71	0.71	4.47	
+12.0	2.00	0.13	0.13	0.26	0.085	0.085	0.17	0.71	0.71	1.42	
No.1	8.00	0.13	0.13	1.04				0.71	0.71	5.68	
合計	20.00			2.60m3			0.71m3			14.20m2	

舗装工											1号箇所
数 量 計 算 書											
測 点	距 離	表層									摘要
		幅	平 均	m2							
B.P		0.50									
+10.0	10.00	0.50	0.50	5.00							
No.1	10.00	0.50	0.50	5.00							
合計	20.00			10.00m2							

土工数量計算書											2号箇所
測 点	距 離	床掘			埋戻 (RC-40)			路肩整正 (RC-40)			摘要
		断面積	平 均	m3	断面積	平 均	m3	幅	平 均	m2	
B.P		0.35			0.35						
No.1	20.00	0.35	0.35	7.00	0.35	0.35	7.00				
+7.3	7.30	0.35	0.35	2.56	0.35	0.35	2.56	0.40			
No.2	12.70	0.35	0.35	4.45	0.35	0.35	4.45	0.40	0.40	5.08	
E.P(+13.6)	13.60	0.35	0.35	4.76	0.35	0.35	4.76	0.40	0.40	5.44	
合計	53.60			18.77m3			18.77m3			10.52m2	

コンクリート工 数量計算書 2号箇所											
測 点	距 離	天端コンクリート									摘要
		断面積	平 均	m3							
B.P		0.06									
No.1	20.00	0.06	0.06	1.20							
No.2	20.00	0.06	0.06	1.20							
E.P(+13.6)	13.60	0.06	0.06	0.82							
合計	53.60			3.22m2							

目地材	0.5×0.12×7	0.42	m2	
-----	------------	------	----	--

2号箇所 構造物取壊し 数 量 計 算 書											
測 点	距 離	無筋Co									摘要
		断面積	平 均	m3							
B.P		0.06									
No.1	20.00	0.06	0.06	1.20							
No.2	20.00	0.06	0.06	1.20							
E.P(+13.6)	13.60	0.06	0.06	0.82							
合計	53.60			3.22m3							

足場	$(1.9+75.0+1.9+75.0) \times 1.15$	176.87	掛m2	
----	-----------------------------------	--------	-----	--