

数量総括表(R8-路3-01)

No.	施工 区分	舗装 構成	上層路盤		表 層		舗装版破碎		As殻処分		舗装版切断		溶融式区画線				
			(不陸整正) 粒調碎石(M30-0) 補足材 (t=3cm)	(PK-3使用) 人力施工 再生密粒度アスコン (t=5cm)	人力施工	人力積込	(t=15cm以下)	白線 (W=15cm)	中心線 (黄、リブ付) (W=20cm)	ゼブラ (停止線 横断歩道) (W=45cm)	最高速度 20(黄) (W=15cm)	グリーン塗装 (2回塗り)					
1	昼	A (5cm)	8.7 m ²	8.7 m ²	8.7 m ²	0.44 m ³	4.62 m	1.60 m		2.3 m							
2	昼	A (5cm)	32.1 m ²	32.1 m ²	32.1 m ²	1.61 m ³	16.70 m	12.0 m	6.0 m								
3	昼	A (5cm)	6.3 m ²	6.3 m ²	6.3 m ²	0.32 m ³	7.50 m										
4	昼	A (5cm)	9.5 m ²	9.5 m ²	9.5 m ²	0.48 m ³	7.10 m										
5	昼	A (5cm)	2.5 m ²	2.5 m ²	2.5 m ²	0.13 m ³	3.55 m										
			3.6 m ²	3.6 m ²	3.6 m ²	0.18 m ³											
			1.1 m ²	1.1 m ²	1.1 m ²	0.06 m ³											
6	昼	A (5cm)	12.9 m ²	12.9 m ²	12.9 m ²	0.65 m ³	6.40 m										
7	昼	A (5cm)	8.9 m ²	8.9 m ²	8.9 m ²	0.45 m ³	6.90 m										
8	昼	A (5cm)	13.5 m ²	13.5 m ²	13.5 m ²	0.68 m ³	10.00 m										
			36.2 m ²	36.2 m ²	36.2 m ²	1.81 m ³											
			17.4 m ²	17.4 m ²	17.4 m ²	0.87 m ³											
9	昼	A (5cm)	15.9 m ²	15.9 m ²	15.9 m ²	0.80 m ³	7.50 m										
10	昼	A (5cm)	15.9 m ²	15.9 m ²	15.9 m ²	0.80 m ³	3.90 m										
11	昼	A (5cm)	36.9 m ²	36.9 m ²	36.9 m ²	1.85 m ³	6.90 m										
12	昼	A (5cm)	7.2 m ²	7.2 m ²	7.2 m ²	0.36 m ³	6.60 m										
13	昼	A (5cm)	19.1 m ²	19.1 m ²	19.1 m ²	0.96 m ³	7.40 m										
14	昼	A (5cm)	8.3 m ²	8.3 m ²	8.3 m ²	0.42 m ³	7.30 m										
15	昼	A (5cm)	20.0 m ²	20.0 m ²	20.0 m ²	1.00 m ³	2.80 m	12.36 m									
			3.8 m ²	3.8 m ²	3.8 m ²	0.19 m ³											
			3.7 m ²	3.7 m ²	3.7 m ²	0.19 m ³											
			1.5 m ²	1.5 m ²	1.5 m ²	0.08 m ³											
			3.1 m ²	3.1 m ²	3.1 m ²	0.16 m ³											
			1.6 m ²	1.6 m ²	1.6 m ²	0.08 m ³											
16	昼	A (5cm)	10.2 m ²	10.2 m ²	10.2 m ²	0.51 m ³	8.50 m	2.40 m					1.0 m ²				
17	昼	A (5cm)	19.6 m ²	19.6 m ²	19.6 m ²	0.98 m ³	5.99 m					18.49 m					
昼間施工 合計			319.5 m ²	319.5 m ²	319.5 m ²	16.06 m ³	119.7 m	28.4 m	6.00 m	2.3 m	18.49 m	5.90 m ²					
改め			320 m ²	320 m ²	320 m ²	16 m ³	120 m	28 m	6 m	2 m	18.49 m	5.9 m ²					

※収集濁水量(m³) : 0.14